



COVINA-VALLEY

UNIFIED SCHOOL DISTRICT

District Superintendent
Richard M. Sheehan, Ed.D.

Board of Education
Sonia Frasquillo
Charles M. Kemp
Sue L. Maulucci
Darrell A. Myrick
Richard M. White

May 10, 2016

ADDENDUM NO. 2

TO: ALL BIDDERS

PROJECT: COVINA-VALLEY UNIFIED SCHOOL DISTRICT
Roofing at Traweek, Northview and South Hills 15-16-115

SUBJECT: SPECIFICATIONS

Page 1 of 2

THIS ADDENDUM IS ISSUED AS PART OF THE CONTRACT DOCUMENTS FOR THIS PROJECT AND AMENDS ONLY THOSE ITEMS SPECIFICALLY DEFINED HEREIN. THIS ADDENDUM MUST BE ATTACHED TO THE INSIDE FRONT COVER OF YOUR SET OF SPECIFICATIONS.

In preparing bids, the bidder shall take into consideration the following items. Information shown herein supersedes requirements issued under previous date.

ASBESTOS AND LEAD CLARIFICATION

The following material were found positive at South Hills HS:

ASBESTOS INFORMATION

500 Building (A4):

*Roof penetration mastic (40 SF): The roof penetration mastic located at seams, patches, penetrations, pipes, vents, and flashing tested positive for asbestos content.

100 Building:

*Roof penetration mastic (70 SF): The roof penetration mastic located at North and East Mechanical rooms seams, patches, penetrations, pipes, vents, and flashing tested positive for asbestos content.

400 Building (A4):

*Roof penetration mastic (50 SF): The roof penetration mastic located at seams, patches, penetrations, pipes, vents, and flashing tested positive for asbestos content.

Normally, asbestos-containing material found to be in good condition is not considered a hazard, unless it is disturbed. Prior to the start of any activity, such as remodeling, demolition, or renovation, that might disturb this material, a Certified Asbestos Consultant should be contracted to design and monitor the project. A California licensed asbestos contractor should be hired to complete the asbestos abatement procedures.

LEAD INFORMATION:

100 Building

No regulated lead-based paint was identified on the exterior surfaces and/or components anticipated to be impacted by the roofing replacement project in the North and East Mechanical Rooms.

400 Building (A2)

Roof top I Beam Metal 300 Linear Feet POSITIVE FOR LEAD

500 Building (A4)

519 E. Badillo Street • Covina, California 91723
626.974.7000 • FAX 626.974.7032
www.cvusd.k12.ca.us

QUESTIONS AND CLARIFICATIONS

Question: Please confirm if the DVBE goal is 3% for this project. We didn't see a percent noted in the instructions.

Clarification: Yes, Education Code sections 17076.11, 100615, 100815 and 101011 require that we establish a participation goal for Disabled Veteran Business Enterprise (DVBE) of at least three percent (3%).

END OF ADDENDUM